

Natl. Cost Code	Material	Description	Qty.	UOM	Waste	Sub. Category
	*** CONCRETE ***					
	*** Footings ***					
25240	Monolithic Footing	3 3/4"x12"	5	cuyd	5.00	001001
	*** Slabs ***					
25240	Concrete Slab (Found.)		88	cuyd	5.00	001001
25230	Found. Sub Base - 2"Sand		28	Tons	—	001002
25230	Found. Sub Base - ABC		61	Tons	—	001002
25310	Wire Mesh (Slab)		3256	sqft	—	001005
	*** Misc. Foundation ***					
25270	PT Cable	41'9 7/8"x11 1/2"	10	each	—	001004
25270	PT Cable	39'1 5/8"x11 1/2"	2	each	—	001004
25270	PT Cable	39'1 1/4"x11 1/2"	1	each	—	001004
25270	PT Cable	39'1 7/8"x11 1/2"	2	each	—	001004
25270	PT Cable	39'2 1/4"x11 1/2"	1	each	—	001004
25270	PT Cable	70'3 1/2"x11 1/2"	6	each	—	001004
25270	PT Cable	17'10 9/16"x11 1/2"	6	each	—	001004
25270	PT Cable	61'6 1/4"x11 1/2"	3	each	—	001004
25270	PT Cable	61'6 3/4"x11 1/2"	1	each	—	001004
25270	PT Cable	38'5 13/32"x11 1/2"	6	each	—	001004
25270	PT Cable	24'1 1/2"x11 1/2"	1	each	—	001004
25270	PT Cable	24'1 7/8"x11 1/2"	1	each	—	001004
25270	PT Cable	24'1 1/8"x11 1/2"	1	each	—	001004
25270	PT Cable	57'3 3/4"x11 1/2"	4	each	—	001004
25270	PT Cable	57'3 7/8"x11 1/2"	2	each	—	001004
25270	PT Cable	57'3 3/8"x11 1/2"	1	each	—	001004
25270	PT Cable	57'3 1/4"x11 1/2"	1	each	—	001004
25270	PT Cable	57'4 1/4"x11 1/2"	1	each	—	001004
25270	PT Cable	57'4 3/4"x11 1/2"	6	each	—	001004
25270	PT Cable	16'5 29/32"x11 1/2"	3	each	—	001004
	*** Reinforcing ***					
25310	Slab Mesh		3256	sqft	—	001003
25260	Anchor Bolts		92	each	—	007004
25310	Rebar (Mono)		825	lin ft	—	001003
25310	PT Cable Chairs		543	each	—	001004
25310	PT Slab Perim. Rebar		532	lin ft	—	001004
	*** FRAMING ***					
	*** 1st DROP					
27280	Plate - Wall 2x4 (1)	2"x4"x16'0"	78	each	5.00	002096
27280	Plate - Wall 2x6 (1)	2"x6"x16'0"	8	each	5.00	002113
27280	Plate - Treated 2x4 (1)	2"x4"x16'0"	25	each	—	002096
27280	Plate - Treated 2x6 (1)	2"x6"x16'0"	5	each	—	002113
27280	Stud -2x4 PC(104 5/8")(1)	2"x4"x104 5/8"	261	each	5.00	002091
27280	Stud -2x4 PC(105 5/8")(1)	2"x4"x105 5/8"	194	each	5.00	002092
27280	Stud -2x6 PC(104 5/8")(1)	2"x6"x104 5/8"	24	each	5.00	002108
27280	Stud -2x6 PC(105 5/8")(1)	2"x6"x105 5/8"	17	each	5.00	002109
27280	Stud - Wall 2x4x10' (1)	2"x4"x10'0"	72	each	5.00	002088
27280	Stud - Wall 2x4x12' (1)	2"x4"x12'0"	30	each	5.00	002094
27280	Stud - Wall 2x6x10' (1)	2"x6"x10'0"	8	each	5.00	002105
27280	Stud - Wall 2x6x14' (1)	2"x6"x14'0"	4	each	5.00	002112
27280	Stud - Wall 2x6x20' (1)	2"x6"x20'0"	7	each	5.00	002115
27280	Stud - 2x4 Total RL(1)	2"x4"	602	lin ft	5.00	002103
27280	Stud - 2x6 Total RL(1)	2"x6"	55	lin ft	5.00	002120
27280	Stud - Jack 2x4 (1)	2"x4"x8'0"	34	each	—	002103
27280	Stud - Jack 2x4 (1)	2"x4"x9'0"	28	each	—	002103
27280	Stud - Jack 2x4 (1)	2"x4"x7'0"	4	each	—	002103

Report Style: Desert - Major Trades

Wednesday, November 01, 2006, 09:55 AM

Natl. Cost Code	Material	Description	Qty.	UOM	Waste	Sub. Category
27280	Stud - Jack 2x6 (1)	2"x6"x8'0"	6	each	—	002120
27280	Stud - Jack 2x6 (1)	2"x6"x9'0"	10	each	—	002120
27280	Stud - Jack 2x6 (1)	2"x6"x18'0"	4	each	—	002120
27280	Header - Glulam (1)	3 1/8"x7 1/2"	8	lin ft	—	004000
27280	Header - Glulam (1)	3 1/2"x3 1/8"	6	lin ft	—	004000
27280	Header - Glulam (1)	3 1/8"x10 1/2"	9	lin ft	—	004000
27280	Header - Glulam (1)	3 1/8"x9"	2	lin ft	—	004000
27280	Sill - Rough (1)	2"x6"	38	lin ft	5.00	002000
27280	Sill - Rough (1)	2"x4"	88	lin ft	5.00	002000
27340	Sheathing - Shear Panels		1461	sqft	—	006000
27250	Brace - Utility 14'	2"x4"x14'0"	36	each	5.00	002095
27250	Brace - Utility 10'	2"x4"x10'0"	48	each	5.00	002088
27250	Lid Backing (2x4)	2"x4"x14'0"	3	each	5.00	002096
27250	Beam - Glm 3.125"x7.5"(1)	3 1/8"x7 1/2"	7	lin ft	—	004085
27250	Lid Backing (2x6)	2"x6"x14'0"	18	each	5.00	002113
27250	Blocking - Wall 2x4	2"x4"	823	lin ft	—	002103
27250	Blocking - Wall 2x6	2"x6"	47	lin ft	—	002120
27250	Beam - Glm 3.125"x15"(1)	3 1/8"x15"	22	lin ft	—	004090
27250	Beam - Glm 5.125"x12"(1)	5 1/8"x12"	12	lin ft	—	004101
27250	Beam - Glm 6.75"x18"(1)	6 3/4"x18"	20	lin ft	—	004120
27220	Sill Seal 50'	4"x50'0"	8	rolls	—	032001
27220	Sill Seal 50'	6"x50'0"	1	rolls	—	032001
	*** 1st Sub. Floor***					
27220	Trusses - Floor (1)	20"x22'0"	20	each	—	004000
27220	Trusses - Floor (1)	20"x18'0"	7	each	—	004000
27220	Trusses - Floor (1)	20"x4'0"	2	each	—	004000
27220	Trusses - Floor (1)	20"x26'0"	1	each	—	004000
27220	Trusses - Floor (1)	20"x12'0"	6	each	—	004000
27220	Trusses - Floor (1)	20"x29'0"	5	each	—	004000
27220	Trusses - Floor (1)	20"x25'0"	5	each	—	004000
27220	Joist - Floor (Dimen.)(1)	2"x8"	15	lin ft	3.00	002000
27220	Joist - Floor (Dimen.)(1)	2"x12"	22	lin ft	3.00	002000
27340	Sheathing - Floor T&G (1)	0 3/4"x4'0"x8'0"	1	shts	7.00	006004
27340	Sheathing - Floor T&G (1)	0 23/32"x4'0"x8'0"	2	shts	7.00	006004
27340	Sheathing - Floor T&G (2)	0 23/32"x4'0"x8'0"	67	shts	7.00	006004
27250	Adhesive 1 -Floor (30oz.)		19	tubes	7.00	007009
	*** 2nd DROP***					
27290	Plate - Wall 2x4 (2)	2"x4"x16'0"	96	each	5.00	002096
27290	Plate - Wall 2x6 (2)	2"x6"x16'0"	3	each	5.00	002113
27290	Stud - 2x4 PC(92 5/8")(2)	2"x4"x92 5/8"	145	each	5.00	002101
27290	Stud - 2x4 PC(93 5/8")(2)	2"x4"x93 5/8"	225	each	5.00	002102
27280	Stud - 2x6 PC(93 5/8")(2)	2"x6"x93 5/8"	12	each	5.00	002102
27290	Stud - Wall 2x4x10' (2)	2"x4"x10'0"	117	each	5.00	002088
27290	Stud - Wall 2x6x10' (2)	2"x6"x10'0"	6	each	5.00	002105
27290	Stud - 2x4 Total RL(2)	2"x4"	835	lin ft	5.00	002103
27290	Stud - 2x6 Total RL(2)	2"x6"	42	lin ft	5.00	002120
27290	Stud - Jack 2x4 (2)	2"x4"x7'0"	58	each	—	002103
27290	Stud - Jack 2x4 (2)	2"x4"x9'0"	18	each	—	002103
27290	Stud - Jack 2x4 (2)	2"x4"x8'0"	34	each	—	002103
27290	Sill - Rough (2)	2"x4"	162	lin ft	5.00	002000
27250	Beam - Glm 3.125"x12"(2)	3 1/8"x12"	23	lin ft	—	004088
27250	Beam -Glm 3.125"x13.5"(2)	3 1/8"x13 1/2"	20	lin ft	—	004089
27290	Beam - Solid Lumber (2)	4"x10"	10	lin ft	—	003000
	*** 3rd DROP ***					
	*** Roof Framing ***					
27220	Fascia 2x6 (Eave)	2"x6"	319	lin ft	5.00	002120
27220	Fascia Sub - 1x3 (Eave)	1"x3"	319	lin ft	5.00	002030

Natl. Cost Code	Material	Description	Qty.	UOM	Waste	Sub. Category
27220	2x4 Outlookers	2"x4"x16'0"	8	each	5.00	002096
27220	2x4 Nailer (Eave)	2"x4"x16'0"	20	each	5.00	002096
27220	2x4 Bird Block (Eave)	2"x4"x14'0"	23	each	5.00	002095
27220	2x4 Hip/Ridge Start	2"x4"	203	lin ft	5.00	002103
27220	Fascia 2x6 (Gable)	2"x6"	239	lin ft	5.00	002120
27310	Slide Guard - 2x4	2"x4"	303	lin ft	—	002103
27310	Slide Guard - 2x6	2"x6"	303	lin ft	—	002103
27340	Sheathing - Roof (4x8)	4'0"x8'0"x0 15/16"	126	shts	—	006001
27340	Sheathing - Plysawn		15	shts	—	006001
	*** Backout Pack ***					
27340	Backout - 4x8x7/16 OSB	4'0"x8'0"x5 5/8"	5	shts	—	006001
27340	Backout - 4x8x23/32 T&G	4'0"x8'0"x0 23/32"	2	shts	—	006004
27250	Backout -2x4 PC(104 5/8")	2"x4"x104 5/8"	13	each	—	002091
27250	Backout -2x4 PC(105 5/8")	2"x4"x105 5/8"	10	each	—	002092
27250	Backout -2x6 PC(104 5/8")	2"x6"x104 5/8"	2	each	—	002108
27250	Backout -2x6 PC(105 5/8")	2"x6"x105 5/8"	1	each	—	002109
27250	Backout - 2x4 PC(92 5/8")	2"x4"x92 5/8"	7	each	—	002101
27250	Backout -2x4 PC(93 5/8")	2"x4"x93 5/8"	11	each	—	002102
27250	Backout -2x6 PC(93 5/8")	2"x6"x93 5/8"	1	each	—	002119
27250	Backout - 2x4x14'	2"x4"x14'0"	4	each	—	002095
27250	Backout - 2x6x14'	2"x6"x14'0"	2	each	—	002112
27250	Backout - 2x8x14'	2"x8"x14'0"	2	each	—	002124
27250	Backout - 2x10x14'	2"x10"x14'0"	1	each	—	002132
	*** ROOFING ***					
	*** Roof Dry-in ***					
33210	Roof Vents		27	each	—	029100
33210	Roofing Felt (single)		10	rolls	—	015004
	*** Roof Finishes ***					
33220	Concrete Tiles Flat		10	squares	6.00	015001
	*** Roof Flashing ***					
34210	Roof "L" Flashing		60	lin ft	—	016002
34210	Roof "Z" Flashing		95	lin ft	—	016003
33230	Metal Edge		303	lin ft	—	015007
34210	Valley Metal		26	lin ft	—	016001
	*** EXTERIOR FINISHES ***					
	*** Exterior Trim ***					
31510	Siding - Soffit Text. lap	0 7/16"x12"x16'0"	35	each	5.00	018000
31510	Siding - Fascia 8"	0 7/16"x8"x16'0"	20	each	3.00	018000
31510	Siding - Fascia 9 1/2"	0 7/16"x9 1/2"x16'0"	15	each	3.00	018000
31510	Trim - 1x4 Gable Frieze	1"x4"x16'0"	16	each	7.00	018000
27220	2x6 #2 R/L (Primed)	2"x6"	34	lin ft	5.00	002120
31510	Text. Siding Corners		29	each	3.00	018000
34210	Vent - 4"x16" Soffit	4"x16"	36	each	—	029300
31980	Building Paper (JumboTex)	40"x100'0"	21	rolls	3.00	018153
31980	Adhesive (10 oz Caulk)		31	tubes	3.00	007009
	*** Stucco ***					
31210	Total Stucco		558	sqyd	—	018000
31210	Stucco Sand		2937	lbs	—	018110
31210	Stucco Cement	80'0"	92	Bags	—	018002
31980	Lap Tape		66	rolls	—	018155
31980	Cap Nails		2	box	—	018000
31980	Window Wrap		16	rolls	—	018002
31980	Window Sealant		49	tubes	—	018002

Natl. Cost Code	Material	Description	Qty.	UOM	Waste	Sub. Category
31210	Power Wall Stucco Foam 1"		134	shts	—	018149
31210	Lath Netting		13	rolls	—	018150
31210	Stucco Corner Aid		385	lin ft	—	018152
31210	Color Coat		558	sqyd	—	018100
31210	Weep Screed		540	lin ft	—	018154
	*** Flashing ***					
34210	Flashing - 1 1/4" "Z"	1 1/4"x8'0"	25	each	5.00	016003
34210	Flashing - 1 3/4" "Z"	1 3/4"x8'0"	3	each	5.00	016003
31510	Flashing - Forti-Flash	9"x75'0"	16	rolls	5.00	035001
	*** INTERIOR FINISHES ***					
	*** Drywall ***					
42210	Board Wall (4x12)	4'0"x12'0"x0 1/2"	203	shts	2.50	019002
42210	Board Ceiling (4x12)	4'0"x12'0"x0 1/2"	82	shts	2.50	019010
42210	Board MR 1/2" (4x12)	4'0"x12'0"x0 1/2"	17	shts	2.50	019008
42210	Board Fire Rated (4x12)	4'0"x12'0"x0 5/8"	14	shts	2.50	019004
42210	Board Ceiling Typ- X 4x12	4'0"x12'0"x0 5/8"	13	shts	2.50	019004
42210	Board Brown 1/2" (4x12)	4'0"x12'0"x6'0"	7	shts	2.50	019013
42210	Drywall Compound		52	box	2.50	019016
42210	Drywall Shims		4	bund	2.50	019017
42210	Quick Set Mud. (20lbs)		4	Bags	5.00	019016
42210	Drywall Screws (25lbs Bx)		3	box	5.00	019022
42210	Drywall Tape (500' rl.)		15	rolls	5.00	019023
42210	Drywall Adhesive (29oz)		103	tubes	5.00	019024
42210	Texture (lt. OP)		24	Bags	5.00	019025
42210	Texture (Med.OP)		30	Bags	5.00	019025
42210	Texture (Hvy Knockdown)		42	Bags	5.00	019025
42210	Bead Window		75	each	5.00	019018
42210	Bead Corner		131	each	5.00	019019
42210	Bead Flex Square nose		22	each	5.00	019020
42210	Bead Flex Bull nose		22	each	5.00	019021
	*** INSULATION ***					
	R-13 Wall Insulation	3 1/2"	3645	sqft	—	
	R-19 Wall Insulation	5 1/2"	346	sqft	—	
	*** PAINT ***					
	Exterior Paint		29	gal	—	
	Interior Paint (Ceiling)		15	gal	—	